

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20562-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 5-13S-33W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: JACK LEE Well #: 1-5
County: LOGAN Total Vertical Depth: 4650 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		4650		
PROD	4.5	4593	0	165 SX
SURF	8.625	207	0	140 SX

151.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2008 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TISHA L. LOVE Company: CASTELLI EXPLORATION, INC. Phone: (405) 722-5511

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 500# hulls - 18 sxs gel.
Plug through casing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2008 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 207' w/140 sxs cement.
4 1/2" production casing set at 4593' w/165 sxs cement.
PBTd 4650'. TD 4650'. DV tool at 2650' w/400 sxs cement.
Deep casing holes.
Connected to 4 1/2" production casing - pumped 50 sxs cement with 500# hulls - 18 sxs gel and 120 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.
Connected to 8 5/8" surface casing - pumped 5 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4521	4531		

INVOICED
DATE 1-16-08
INV. NO. 2008061053

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 14 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENTING COMPANY-TICKET #1755. 38.94803 - 101.01720.

Plugged through: CSG

District: 04

10

Signed Darrel Dipman
(TECHNICIAN)

PE

JAN 10 2008

replacement card

5-13S-33W
50'S, C NW SW SW

WANKER OIL
WAKEENEY KS 67672

1-5 JACK LEE

API 15-109-20562

site	2-1/4 N & 8 E OF RUSSELL SPRINGS KS	by	LOGAN	API	15-109-20562
contr.	EMPHASIS OIL OPER # 8	field	LOGANSPORT NW EXT (1/8 E)		
oper.	MARK TORR	card	06/20/94	last	
date	01/07/94	date	03/03/94	received	08/14/95

ELV: 3031 KB, 3026 GL LOG

tops	depth/datum
ANH	2469 + 562
HEEB	3901 - 870
TOR	3926 - 895
LANS	3954 - 923
STARK	4195 - 1164
BKC	4272 - 1241
PAW	4388 - 1357
FT SC	4448 - 1417
CHER SH	4475 - 1444
MISS	4608 - 1577
LTD	4649 - 1618
RTD	4650 - 1619

IP STATUS
OIL, P 65 BOPD, NW, CHER 4521-4531, 03/22/94
CORR & INFO REL: 8/14/95 - ORIG FR IN NW SW SW
(CORR PER GEO RPT). WAS OIL WELL - TIGHT HOLE
NOTE: CORR 1/12/94 - ORIG FR IN 15-13-33W (CORR BY OPER)
CSG: 8-5/8" 207 / 140 SX (ALT 2), 4-1/2" 4593 / 565 SX,
DV TOOL AT 4650 / 400 SX
NO CORES
DST (1) 3973-4000 (LKC), / 45-60-45-60, REC 62 MW,
124' WM ISIP 1028# FSP 1028# IFF 21# -60# FFP 68#
-87#

DST (2) 4102-4135 (LKC), / 30-30-30-30, REC 20' WM ISIP 1206# FSP 1168# IFF 23# -28# FFP 30# -32#
DST (3) 4138-4171 (LKC), / 15-15-5-0, REC 10' OIL SPTD M ISIP 1165# IFF 27# -28# FFP 28# -28#
DST (4) 4190-4236 (LKC), / 15-15-5-0, REC 10' M ISIP 1165# FSP 29# IFF 30# -30# FFP 30#
DST (5) 4486-4540 (CHER, JOHNSON ZN), / 30-30-30-30, REC 105' GSY OIL, 93' GSY MCO, 62' G & OGM ISIP 510# FSP 507# IFF 32# -69# FFP 80# -110#
TRGT ZN: LKC, JOHNSON ZN, PTD 4590 (MISS), MICT - CO, PF (JOHNSON ZN) 4521-4531, W / 3 SPF, AC 1750 GAL (15% NE), GSO, SET 2-3/8" TBG AT 4648, NO PKR, POP, P 65 BOPD, NW, 3/22/94