

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20444-00-01
Spot: SW Sec/Twnshp/Rge: 26-28S-8W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: JULIA TUNNEY Well #: 1
County: KINGMAN Total Vertical Depth: 4129 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: 414 PLAZA DR STE 204
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4124		100 SX
SURF	8.625	270		100 SX
T1	2.375	4100		

134.19

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/14/2007 8:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EPLORATION Phone: (620) 786-9166

Proposed
Plugging
Method:

PER KCC RULES

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 11/15/2007 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

11/14/07 - CIBP SET AT 4085' - 2 SACKS OF CEMENT PLACED ON TOP.
PERFORATED CASING AT 1175', SET PACKER AT 1075' PUMPED 50+ SACKS
THROUGH TUBING, WAITED 2 HOURS TAGGED CEMENT. RAN TUBING INTO 800'
AND CIRCULATED TO SURFACE. 11/15/07 CHECK TOP PLUG, IT FELL BACK TO
370', RAN IN 2 INCH POLY AND CIRC TO SURFACE. CUT WINDOWS IN SURF
CASING TO CHECK FOR CEMENT, VERIFIED THAT THERE WAS CEMENT ON THE
BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4124	4129		
INVOICED			
DATE <u>1-16-08</u>			
INV. NO. <u>2008061066</u>			
RECEIVED KANSAS CORPORATION COMMISSION			
JAN 10 2008			
CONSERVATION DIVISION WICHITA, KS			

Remarks: FIRST 50 SACKS 60/40 POS MIX 4% GEL WITH 3% C.C. THE NEXT 300 SACKS WERE 60/40 POS MIX 4% GEL. TICKET #21296 Allied - medicine lodge, ks

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

PKT