

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19127-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 32-20S-12W  
3656 feet from S Section Line, 3124 feet from E Section Line  
Lease Name: DEWERFF B Well #: 3  
County: BARTON Total Vertical Depth: 3525 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1130  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3519	0	100 SX
SURF	8.625	251	0	250 SX

114.56

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/26/2007 10:00 AM  
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.  
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 792-2222

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 600# hulls - 8 sxs gel.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/31/2007 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

12/26/2007  
Ran tubing in 2875' - tied to tubing - pumped 50 sxs cement with 100# hulls.  
Pulled tubing to 2570' - tied to tubing - pumped 8 sxs gel with 200# hulls.  
Pulled tubing to 1550' - tied to tubing - pumped 50 sxs cement with 100# hulls.  
Pulled tubing to 600' - tied to tubing - pumped 150 sxs cement with 200# hulls - shut down.  
12/27/2007  
Tagged cement with tubing to 1270'.  
Pulled to 1210' - pumped 200 sxs cement.  
Pulled to 580' - pumped 100 sxs cement - got circulation on backside with 1000# hulls.  
Shut down - out of cement.  
12/31/2007  
Tagged cement with tubing at 400' - pumped 40 sxs cement with 100# hulls - circulated to the top.  
Pulled tubing - squeezed 500 P.S.I. Shut in.

Perfs:

Top	Bot	Thru	Comments
3505	3509		

INVOICED

DATE 1-10-08  
INV. NO. 2008061032

RECEIVED  
JAN 7 2008  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #31008. 38.27092 - 98.67435.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

E K EDMISTON

#3 DEWERFF 'B'

32-20-12W  
NE SE NW 53

Contr. E K EDMISTON BARTON County

E1858 RB Comm. 1-5-62 Comp. 5-17-62 IP 25 BOPD/ARB 3505-09

Tops	Depth	Datum	Casing
HEEB	3066	-1208	8" 25' 4" 3519
BR LM	3190	-1332	DST 3366-81/75", 40' MDY W, BHP 1168-1040# DST 3385-3405/90", G/80", 90' o, 120' SL OCW, 300' W, BHP 1115-1025#
LANS	3206	-1348	DST 3483-96/90", 10' H OCM, 60' MDY W, BHP 622-586#
B/KC	3421	-1564	DST 3497-3525/90", 185' GIP, 1450' o, 60' W, BHP 732-673#
CONG CHERT	3441	-1583	PERF 16/3505-09: 350' OIH/12 HRS, NW: 650' FLD/24 HRS (40' MDY W) SWB 1 BO/1ST HR: ACID 250: SWB 7 BFPH, 10% WTR: FU 2200' FLD/12 HRS, (1950' o & 250' w)
ARB	3468	-1610	
TD	3525	-1667	

ROLLING GREEN EAST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS