

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20623-00-01
Spot: N2S2SE Sec/Twnshp/Rge: 13-15S-12W
990 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HEINZE A Well #: 4
County: RUSSELL Total Vertical Depth: 3330 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3331	0	w/unknown sxs cmt
SURF	8.625	257	0	w/155 sxs cmt

108.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/02/2008 2:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TERRY MORRIS Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf at 300' - 750' - 1100'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2008 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 2510' - tied to tubing - pumped 60 sxs cement with 100# hulls.
Pulled to 1310' - pumped 100 sxs cement with 200# hulls.
Pulled to 660' - pumped 50 sxs cement with 200# hulls - circulated to the top.
Pulled tubing - topped off with 5 sxs cement.
Tied to backside - squeezed with 25 sxs.

Perfs:

INVOICED
DATE 1-10-08
INV. NO. 2008061036

RECEIVED
JAN 07 2008
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING-TICKET #1734. 38.74327 - 98.60234.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

100

JAN 04 2008

PKT

