

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-12123-00-01

Spot: NENWNW

Sec/Twnshp/Rge: 25-20S-12W

4950 feet from S Section Line,

4290 feet from E Section Line

Lease Name: L. M. JACKSON

Well #: 1

County: BARTON

Total Vertical Depth: 3351 feet

Operator License No.: 3911

Op Name: RAMA OPERATING CO., INC.

Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3327	2400	100 SX
SURF	8.625	593	0	375 SX

108.91

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/26/2007 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed
Plugging
Method:

Ordered 225 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/26/2007 1:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded casing to 3180' - topped with 5 sxs 60/40 pozmix - 4% gel.
Cut casing at 2400' - pulled to 1050'.
Tied to casing - pumped 100 sxs cement with 200# hulls.
Pulled casing to 600' - pumped 60 sxs cement with 200# hulls.
Pulled to 80' - circulated to top with 25 sxs cement and 100# hulls.
Stayed full.

Perfs:

Top	Bot	Thru	Comments
3335	3340		
3234	3242		

INVOICED
DATE 1-10-08
INV. NO. 2008061043

RECEIVED
JAN 07 2008
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #31007. 38.28924 - 98.60524.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

JAN 02 2008

TEXACO, INC.
P.O. BOX 2420
TULSA, OK 74102

#1 L.M. JACKSON 'OWWO'


25-20-12W
NE NW NW

CONTR UNKNOWN

CTY BARTON

GEOL

FIELD CHASE-SILICA



ELV 1813 KB SPD 2/1/83 CARD ISSUED 3/24/83 IP P 3 BO & 32 BWPD
1808 GL LKC 3124-3317 OA
API NOT ASSIGNED ARB 3335-3340

SMP	Tops	Depth/Datum
HEEB		2966-1153
LANS		3107-1294
ARB		3335-1522
PBTD		3343-1530
RTD		3351-1838

OLD INFO: OPERATOR WAS TEXAS COMPANY, #1 JACKSON, SPD 11/26/48, SET 8 5/8 " 593 / 375 SX, 5 1/2 " 3327 / 100 SX, COMP. AS P 480 BOPD, ARB OH 3327-3351 12/24/48, CONTR: POWELL-BRUNSON

NO DST'S

MICT - CO, (ARB OH), AC 1000 G, SWB 16.5 BOPH / 12 HRS, RE-AC 2000 G, POP

NEW INFO: PROD DECL, OFF PMP 2/1/83, MICT - CO, PB 3343 TD, PF (U ARB) 3335-3340, AC 250 G, (15% NEA), SWB DWN, GSO, PF (LKC) 3124-3317 OA, AC 1700 G, (15% NEA), SWB DWN, GSO, POP, P 3 BO & 32 BWP, (GR 35.3°), 2/12/83, COM-MINGLED

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

028 - 0 1/1