

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21146-00-01  
Spot: SWNWSE Sec/Twnshp/Rge: 19-12S-20W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WENDLING Well #: 2  
County: ELLIS Total Vertical Depth: 3932 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3927	0	w/250 sxs cmt
SURF	8.625	246	0	w/150 sxs cmt

127.79

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/31/2007 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 800# hulls.  
Rods and tubing stuck in the hole at 2730'.  
Casing leaks at 1345' and 1598'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/31/2007 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 2560' - pumped 75 sxs cement with 300# hulls.  
Pulled tubing to 1300' - pumped 85 sxs cement with 400# hulls.  
Pulled tubing out - squeezed with 15 sxs cement.  
S.I.P. 500#.  
Tied onto backside - squeezed with 10 sxs cement.  
Max. P.S.I. 400#.

Perfs:

Top	Bot	Thru	Comments
3578	3706		

INVOICED


DATE 1-10-08  
INV. NO. 2008061044

RECEIVED  
KANSAS CORPORATION COMMISSION  
**JAN 04 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #24825. 38.99085 - 99.58431.

Plugged through: TBG

District: 04

Signed MB   
(TECHNICIAN)

JAN 02 2008

*PKS*

A. SCOTT RITCHIE  
 412 UNION CENTER, WICHITA, KS. #2 WENDLING

19-12-2GW  
 SW NW SE

CONTR MURFIN DRILG. CO. CTY ELLIS

GEOL \_\_\_\_\_ FIELD KELL

E 2255 KB M 1/12/76 CARD ISSUED 1/6/77 IP P 50 BOPD + TR W  
 ARB 3914-32

+	+	+
+	+	+
+	+	+

API 15-051-21,146

SMP	TOPS	DEPTH	DATUM
ANH		1611	+ 644
B ANH		1650	+ 605
TOP		3273	-1018
HEEB		3504	-1249
TOR		3526	-1271
LANS		3542	-1287
BKC		3788	-1533
MAEM		3839	-1584
ARB		3917	-1662
RTD		3925	-1670
DDTD		3932	-1677

8-5/8" 246/150sx, 4 1/2" 3914/250sx  
 DST (1) 3292-3310/30-45, 165' M W/V FE  
 SP O, SIP 1208# FP 124#  
 DST (2) 3530-3557/30-45-30-45, 15' M,  
 SIP 55-49# FP 24-24#  
 DST (3) 3557-3590/30-30-30-30, 110' O L  
 SP M, 60' HOCM, 480' MO, 60' CO, SI  
 759-759# FP 37-273#  
 DST (4) 3604-3625/30-45-45-45, 125' M  
 SIP 973-902# FP 24-74#  
 DST (5) 3683-3735/30-45-45-45, 670' G  
 40' OIL SP M, 775' MGO, 310' GSY C  
 SIP 926-901# FP 74-447#  
 DST (6) 3732-60/30-45-45-45, 600' W,  
 1235#-1232# FP 18-323#  
 DST (7) 3918-3925/MIS-RUN

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

STATE: KANSAS COUNTY: ELLIS REISSUE OWWO 19-12S-20W  
 FIELD: KELL SW NW SE  
 OPER: RITCHIE EXPL 1650 FSL 2310 FEL SEC  
 WELL: 2 WENDLING WELL CLASS: DO ELEV: 2255 KB  
 API: 15-051-21146-0001 STATUS: OIL-WO 2250 GR  
 SPUD: 10/23/90 COMP: 11/14/90  
 LTD: FTD: ARBUCKLE PBDT:

LOC:

IP: COMP 11/14/90, IPP 7 BOPD, 112 BWPD PROD ZONE- LANSING-KC 3578-3706  
 GROSS ARBUCKLE 3927-3932 OPENHOLE COMMINGLED FIRST REPORT &  
 COMPLETION

CSGS: CMTD 960-991 W/200 SX TO PROTECT CSG; TBG: 2 3/8 @ 3926;  
 OWWO: OWWO: OLD INFO: FORMERLY A SCOTT RITCHIE 2 WENDLING. SPUD 1/12/76. 8  
 5/8 @ 246 W/150 SX, 4 1/2 @ 3927 W/250 SX. SPL TOPS: LANSING 3542,  
 MARMATON 3839, ARBUCKLE 3917. OTD 3932. COMP 12/28/76. IPP 50 BOPD. PROD  
 ZONE: ARBUCKLE 3927-3932 OPENHOLE.

PERFS: (ARBUCKLE) 3927-3932 OPENHOLE PERF (LANSING-KANSAS CITY) 3578-3706  
 W/3 PF, GROSS, ACID W/2250 GALS, 15%

PRODUCING INTERVAL: (ARBUCKLE) 3927-3932 OPENHOLE, PERF (LANSING-KANSAS  
 CITY) 3578-3706 GROSS,

OPER ADD: 125 N MARKET, STE 1000, WICHITA, KS, 67202 PHONE (316) 267-4375;

CONTR: NOT RPTD

WELL ID CHANGES: FINAL CLASS CHGD FROM WSD;

REISSUED TO ADD NEWLY RELEASED CONFIDENTIAL DATA. REPLACEMENT FOR CARD

ISSUED 12/27/91

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 04/03/92 CARD # 00069-KS