

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04964-00-00
Spot: SENENW Sec/Twnshp/Rge: 29-20S-12W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KOMAREK Well #: 1
County: BARTON Total Vertical Depth: 3525 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3525	0	25 SX
SURF	8.625	249	0	250 SX

114.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2008 8:30 AM
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 792-2222

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 1500# hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2008 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3128' - tied to tubing - pumped 100 sxs cement with 250# hulls.
Pulled to 1768' - pumped 60 sxs cement with 200# hulls.
Pulled to 771' - pumped 110 sxs cement with 350# hulls - shut down.
Tagged cement with tubing 728' - pulled back to 671'.
Tied to tubing - pumped 300 sxs cement with 1000# hulls - circulated to surface.
Pulled tubing - pumped 75 sxs cement - came up around surface pipe.
Left cement at surface level.

Perfs:

Top	Bot	Thru	Comments
3466	3472		
3351	3355		
3330	3333		
3251	3256		
3244	3246		
3221	3224		

INVOICED
DATE 1-16-08
INV. NO. 2008061058

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 14 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #3806 & 31015. 38.28726 - 98.67448.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

JAN 11 2008

E K EDMISTON

#1 KOMAREK


29-20-12W 53
SE NE NW

Contr. E K EDMISTON BARTON County

E 1859 RB Comm. Comp. 5-26-61 IP 50 BOPD/ARB

Tops	Depth	Datum
ANH	653	+1206
BR LM	3186	-1327
LANS	3201	-1342
CONG	3443	-1584
ARB	3450	-1591
TD	3525	-1666

Casing
 8" 248
 4" 3525
 DST 3210-85/1 HR, 30", 320' GCM, SPKS O,
 BHP 1180-1125#
 DST 3325-95/2 HR, 300' OC GSY M, 1080'
 MC GSY O, 10' W, BHP 1200-1100#
 DST 3360-95/2 HR, 960' SW, BHP 1150-1000#
 DST 3452-59/90", 30' M, BHP 890-800#
 DST 3461-75/2 HR, 600' GIP, 480' O, SL
 MC, NW, BHP 890-780#
 DST 3481-93, 120' GIP, 60' O, 540' SW,
 BHP 860-640#
 PERF 3466-74: 450' FU/13 HRS: 150' WTR:
 BATCHMAN POOL SWB 1 BOPH, NW: ACID 250
 SWB 5 BFPH, 40% WTR



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

14

15