

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: _____ Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/31/2007 (Date)
by: Marvin Mills (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3926' Bottom: 3932' T.D. 3932'
LKC Depth to Top: 3578' Bottom: 3706' T.D. 3932'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-21146-0001
Lease Name: Wendling
Well Number: 2
Spot Location (QQQQ): _____ - SW - NW - SE
3630 Feet from North / South Section Line
2310 2357 Feet from East / West Section Line
Sec. 19 Twp. 12 S. R. 20 East West
County: Ellis
Date Well Completed: 01/21/1976 11/14/90
Plugging Commenced: 12/31/2007
Plugging Completed: 12/31/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil & Water	3926'	3932'	8.625"	246'	-0-
LKC	Oil & Water	3578'	3706'	4.50"	3926'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing down to 2560'. Pumped 75 sx 60/40 Pozmix w/ 4% gel + 300 hulls, down tubing. Pulled tubing up to 1300'.
Pumped 85 sx 60/40 Pozmix w/ 4% gel + 400 hulls to surface. Pulled tubing out of hole. Topped off 4.50" casing with 15 sx 60/40 Pozmix w/ 4% gel.
Shut in at 500#. Pumped 10 sx 60/40 Pozmix w/ 4% gel down 8.625 casing. Shut in at 400#.


Plugging complete at 12:30 p.m. witnessed and approved by Marvin Mills with the KCC
Name of Plugging Contractor: Express Well Service & Supply Inc License #: 6426
Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick, ss.

Peter J. Fiorini - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 10th day of January, 20 08



Joyce Cochran Notary Public My Commission Expires: 4-10-11

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Per KCC GPS PPT

KCC PPT

KCC PPT 1/13

RECEIVED KANSAS CORPORATION COMMISSION

JAN 11 2008

CONSERVATION DIVISION WICHITA, KS

PPT

ALLIED CEMENTING CO., INC. 24825

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>12-31-07</u>	SEC. <u>19</u>	TWP. <u>12</u>	RANGE <u>20</u>	CALLED OUT	ON LOCATION	JOB START <u>12:00PM</u>	JOB FINISH <u>1:00PM</u>
LEASE <u>Wending</u>		WELL # <u>#2</u>		LOCATION <u>Ellis 3A To Curve</u>		COUNTY <u>Ellis</u>	STATE <u>KANSAS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1 1/2 W 1/2 N INTO</u>		<u>ELLIS</u>	

CONTRACTOR Express Well Service
 TYPE OF JOB Plug ABANDONED well
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2 DEPTH 3927
 TUBING SIZE 2" DEPTH 2560
~~DRILL PIPE~~ 5/8" SURFACE DEPTH 246
 TOOL _____ DEPTH _____
 PRES. MAX 500# MINIMUM 400#
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT (USED 185 SK) 185
 AMOUNT ORDERED 400 SK @ 40 4% GEL
700 # Hullis

COMMON	<u>110 SK</u>	@ <u>11.00</u>	<u>1221.00</u>
POZMIX	<u>75 SK</u>	@ <u>6.20</u>	<u>465.00</u>
GEL	<u>8 SK</u>	@ <u>16.65</u>	<u>133.20</u>
CHLORIDE		@	
ASC		@	
Hullis	<u>7 SK</u>	@ <u>25.50</u>	<u>178.50</u>
HANDLING	<u>416 TOTAL SK</u>	@ <u>1.90</u>	<u>790.40</u>
MILEAGE	<u>50 Tow Mile</u>	@ <u>.095</u>	<u>1872.00</u>
TOTAL			<u>4660.10</u>

REMARKS:

Ran 2" Tubing to 2560' & Spot
75 SK Cement w/ 300# Hullis. Pulled up to
1300 & Circulated Cement to SURFACE
w/ 85 SK & 400 # Hullis. Came out w/
Tubing, & Hooked up to CSG w/ 4 1/2 Swage
& Squeezed in another 15 SK @ 500#
2 5/8" Backside - Squeezed in 10 SK
@ 400# max & Shot in. THANK'S!

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>955.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>50</u>	@ <u>6.00</u>	<u>300.00</u>
MANIFOLD	@	
TOTAL <u>1255.00</u>		

CHARGE TO: RITCHIE EXPLORATION
 STREET _____
 CITY _____ STATE _____ ZIP _____

STATE REP.
MARVIN MILL'S (KCC)
 ON LOCATION.

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

RECEIVED _____
 KANSAS CORPORATION COMMISSION _____
JAN 11 2008
 CONSERVATION DIVISION _____ TOTAL _____
 WICHITA, KS _____
 TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas AAL

PRINTED NAME _____