

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767

Type of Well: _____ Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/19/2007 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss. Osage Open-Hole Depth to Top: 4388' Bottom: 4403' T.D. 4403'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-23971 - 00-01

Lease Name: Schaben P

Well Number: 1 Twin

Spot Location (QQQQ): approx - SW - NE - NE
920 Feet from North / South Section Line

920 Feet from East / West Section Line

Sec. 6 Twp. 20 S. R. 21 East West

County: Ness

Date Well Completed: 02/08/1997 2/21/05

Plugging Commenced: 12/19/2007

Plugging Completed: 12/19/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Miss. Osage Open-Hole	Oil & Water	4388'	4403'	8.625"	336'	-0-
				5.50"	4388'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing down to 4350'. Pumped 50 sx 60/40 Pozmix w/ 4% gel + 200 hulls, down tubing. Shut in with 450 PSI.

Pulled tubing up to 1524'. Pumped 165 sx 60/40 Pozmix w/ 4% gel + 200 hulls down tubing, cement circulating to surface.

Pulled tubing out of hole. Pumped 25 sx 60/40 Pozmix w/ 4% gel down 5.50" casing. Pumped 25 sx 60/40 Pozmix

w/ 4% gel down 8.625 casing. Plugging complete at 12:30 p.m. witnessed and approved by Mike Maier with the KCC

Name of Plugging Contractor: Allied Cementing License #: 99996

Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.

State of Kansas County, Sedgwick, ss.

John Niernberger - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 10th day of January, 20 08

Notary Public _____ My Commission Expires: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

orig.
2/21/05
KCC PKT
PKT

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 11 2008
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

25523

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Great Bend

DATE <u>12-19-07</u>	SEC. <u>10</u>	TWP. <u>20S</u>	RANGE <u>21W</u>	CALLED OUT <u>7:00 AM</u>	ON LOCATION <u>10:30 AM</u>	JOB START <u>3:00 PM</u>	JOB FINISH <u>4:00 PM</u>
LEASE <u>SCHABEN</u>	WELL # <u>1</u>	LOCATION <u>Bazine 75 3/4 S into</u>			COUNTY <u>Ness</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD <input type="radio"/> NEW (Circle one)							

CONTRACTOR <u>H&P W/S</u>	OWNER <u>Ritchie Exploration</u>
TYPE OF JOB <u>OH.P</u>	
HOLE SIZE _____ T.D. _____	CEMENT _____
CASING SIZE <u>5 1/2</u> DEPTH <u>4350'</u>	AMOUNT ORDERED <u>3255x60/HO 4 1/2</u>
TUBING SIZE <u>2 1/2</u> DEPTH <u>4350'</u>	<u>GELT 400# HULLS</u>
DRILL PIPE _____	<u>used 2155x</u>
TOOL _____	
PRES. MAX <u>450</u> MINIMUM <u>100</u>	COMMON <u>159 wt. @ 11.10 1764.90</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX <u>106 wt. @ 6.20 657.20</u>
CEMENT LEFT IN CSG. _____	GEL <u>9 wt. @ 16.65 149.85</u>
PERFS. _____	CHLORIDE _____ @ _____
DISPLACEMENT <u>FRESH WATER</u>	ASC _____ @ _____
EQUIPMENT _____	<u>HULLS 400# @ 25.50 102.00</u>
	_____ @ _____
	_____ @ _____
PUMP TRUCK CEMENTER <u>Dwayne W</u>	_____ @ _____
# <u>181</u> HELPER <u>Wayne D</u>	_____ @ _____
BULK TRUCK _____	_____ @ _____
# <u>344</u> DRIVER <u>Carl S</u>	_____ @ _____
BULK TRUCK _____	_____ @ _____
# _____ DRIVER _____	_____ @ _____
	HANDLING <u>340 wt. @ 1.90 646.00</u>
	MILEAGE <u>340 mi. @ 19 6460.00</u>
	TOTAL <u>3901.35</u>

REMARKS:

1ST PLUG AT 4350' PUMP 50SX AND
200# HULLS THRU 2 1/2 TUBING AND
DISP 15 BBLs FRESH WATER @ 450 PSI
PULLED UP TO 1500' MIX 1655X CEMENT
AND 200# HULLS CIRCULAR TO SURFACE
TOP OF 255X CEMENT PUMP DOWN THE
BACK 255X CEMENT
WASH UP AND RIG DOWN

SERVICE

DEPTH OF JOB <u>4350'</u>	
PUMP TRUCK CHARGE _____	<u>955.00</u>
EXTRA FOOTAGE _____ @ _____	
MILEAGE <u>19</u> @ <u>6.00</u>	<u>114.00</u>
MANIFOLD _____ @ _____	
_____ @ _____	
_____ @ _____	
TOTAL _____	<u>1069.00</u>

CHARGE TO: Ritchie Exploration

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____	@ _____	
_____	@ _____	
_____	@ _____	
_____	@ _____	
_____	@ _____	
TOTAL _____		

Thank You

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE x Bennie Dills

x BENNIE DILLS
PRINTED NAME JD