

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation
Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366
Phone: 316-636-2737 Operator License # 5003
Type of Well: D&A Docket #: NA
The plugging proposal was approved on: 11/20/07 (Date)
by: Lin Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: Bottom: T.D.

API Number 15-047-21563
Lease Name: BUCHANAN TRUST "A"
Well Number: #1-17
Spot Location (QQQQ): N2 N2 SW
2310 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec 17 Twp 26s S. Rng. 17 East West
County: Edwards
Date Well Completed: 11/22/07
Plugging Commenced: 11/22/07
Plugging Completed: 11/23/07

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 309' KB, None.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

11/23/07: Plugged with 120 sacks of 60/40 Pozmix with 4% gel as follows: 50 sack plug at 1140', 50 sack plug at 330', 20 sack plug at 60', cemented to surface. Plugged rathole with 15 sacks and mousehole with 10 sacks.

KCC per CR 7/3

Name of Plugging Contractor: Sterling Drilling Co Basic Energy Services, LP License #: 32453 5142
Address: P.O. Box 8613, Pratt, KS 67124-8613
Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
State of Kansas County, Sedgwick, ss.

Scott Hampel - Vice President, Production (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel
(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 4th day of January 20 08
Brent B Reinhardt My Commission Expires: 12/7/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials 'PRT' in the bottom right corner.