

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sedgwick County. Sec. 4 Twp. 26 Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW  
Lease Owner White & Ellis Drilling, Inc.  
Lease Name Bassett Well No. 1  
Office Address Box 448, El Dorado, Kansas 67042  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 7-30 1962  
Application for plugging filed 4-26-71 8-4- 19 71  
Application for plugging approved 4-27-71 8-4- 19 71  
Plugging commenced 8-19 19 71  
Plugging completed 8-23 19 71  
Reason for abandonment of well or producing formation Loss of production



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 4-29 1971  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey  
Producing formation Burgess Sand Depth to top 2897 Bottom \_\_\_\_\_ Total Depth of Well 2920 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	- - -
				5 1/2"	2919'	2405.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dug out cellar, plugged back 2920' to 2880' with sand & gravel  
Dumped 5 sacks cement at 2895'  
Ripped pipe to 2400'  
Pulled 73 joints 5 1/2" casing  
Put in bridge of sand & gravel 290' to 240'  
Filled hole 240' to 225' with sand & gravel  
Cemented with 4 yds Ready-Mix from 225' to 3'

RECEIVED  
STATE CORPORATION COMMISSION  
9/13/71  
SEP 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.  
Address Box 448, El Dorado, Kansas


STATE OF Kansas, COUNTY OF Butler, ss.  
Ernest Sifford

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford

(Address) \_\_\_\_\_

Subscribed and sworn to before me this 10th day of September, 1971



September 26, 1972

L. B. Auer  
L. B. Auer  
Notary Public.

15-173-03562-00-00 *SR*

Casing Record

8 5/8 2011' Cemented  
w/150 sacks

5 1/2 2019' Cemented  
w/60 sacks

T. D. 2920'

Location: NE SE SW  
Section: 4-26S-2E  
Sedgwick County, Kansas  
Farm: Bassett #1  
Well Owner: White & Ellis Prod., II  
Contractor: White & Ellis Drig., II  
Spudded: 7/20/62  
Under Surface: 7/24/62  
Completed: 7/30/62

Kelly Bushing Measurement 5' above ground level

Elevation: 1392 D.F. 1395 K.B.

FORMATION	DEPTH
Soil	0-10
Lime	35
Shale	50
Lime	65
Shale	75
Lime	120
Shale	130
Lime	145
Shale	150
Lime	175
Shale	185
Lime	200
Shale & Lime stks.	290
Lime	330
Lime & Shale stks.	490
Lime, hd.	530
Lime R. Shale stks.	617
Lime & Shale stks.	1050
Shale & Lime stks.	1270
Lime & Shale stks.	1370
Shale & Shells	1420
Lime, hd. stks.	1462
Shale & Lime stks.	1539
Lime & Shale	1965
Shale & Lime stks.	2035
Lime & Shale stks.	2255
Lime	2300
Shale & Lime stks.	2356
Lime, hd. stks.	2367
Lime & Shale	2463
Lime	2508
Shale	2593
Shale & Lime stks.	2720
Lime & Shale stks.	2830
Shale & Lime	2897
Sand	2920

TOTL

Lansing 2235  
Kansas City 2463  
B/Kansas City 2510  
Burgess 2897

RECEIVED  
STATE DEPARTMENT OF CONSERVATION  
APR 27 1971  
CONSERVATION DIVISION  
Wichita, Kansas