

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

*(Handwritten mark)*

Sedgwick County. Sec. 4 Twp. 26 Rge. 2 (E) (#)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Rock Island Oil & Refg Co. Inc.

Lease Name ~~321 West Douglas~~ Johnson Well No. I

Office Address 321 West Douglas Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed Oct 1963

Application for plugging approved Oct 1963


Plugging commenced Oct 14 1963

Plugging completed Oct 19 1963

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2960' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		<del>2, 18'</del> 2,518'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Covered formation & perforations with sand to 2900'.  
Dumped 50 sx of cement. Set 10' of rock bridge at 200'. Dumped 15 sx cement.  
Set 5' of rock bridge at 29'. Dumped 8 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss. Art Lamb

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 Kings Dr. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 st day of October, 1963

My commission expires January 5, 1966

Judy Lamb  
Notary Public.



15-173-01928-00-00

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Rock Island Oil & Refining Co., Inc.**  
 FARM **Johnson** NO. **1**

SED. **4** T. **26** R. **2E**  
 LOC. **NE NE SW**

TOTAL DEPTH **2960'**  
 COMM. **5-17-61** COMP. **5-25-61**

COUNTY **Sedgwick**  
 KANSAS

SHOT OR TREATED  
 CONTRACTOR **SeRoBee Drilling Co., Inc.**  
 ISSUED



CASING

20	10	
15	8 - 5/8	165' W/100 sacks
12	6	
13	5 - 1/2	2959' W/75 sacks

ELEVATION **1399 GL**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	-	40	Clay, sand & shale
40	-	2374	Shale & lime
2374	-	2640	Lime
2640	-	2909	Lime & shale
2909	-	2915	Sand
2915	-	2918	Shale & sand
2918	-	2960	Chat
		2960	TD

**RECEIVED**  
 STATE CORPORATION COMMISSION

OCT 1 1963

CONSERVATION DIVISION  
 Wichita, Kansas