



WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Sedgwick County. Sec. 4 Twp. 26S Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines CS/2 NW NE

Lease Owner Emil B. Kucera et al

Lease Name Feik Well No. 5

Office Address 404 One Twenty Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed August 14 19 63

Application for plugging filed August 14 19 63

Application for plugging approved August 14 19 63

Plugging commenced August 14 19 63

Plugging completed August 14 19 63

Reason for abandonment of well or producing formation Lack of commercial production.

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation None Depth to top Bottom Total Depth of Well 2912 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 195 feet with 40 viscosity mud.
Set plug @ 195 feet. Put 20 sacks cement on plug.
Mudded hole to 30 feet. Set plug. Put 8 sacks
cement on plug. Put 2 sacks cement in rat hole.
Cut off surface below plow depth and welded plate
on top.

RECEIVED
STATE CORPORATION COMMISSION
8/19/63
AUG 19 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Canaday Drilling Company

Address 6427 East Kellogg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Granville E. Canaday, Jr.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Granville E. Canaday, Jr.
6427 E. Kellogg, Wichita, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of August, 1963

Pat Deasore

Notary Public.

My Commission Expires Jan. 31, 1967

My commission expires _____



15-173-03561-00-00

Q

WELL LOG

COMPANY: Emil B. Kucera et al.
404 One Twenty Bldg.
Wichita, Kansas

COMMENCED: August 8, 1963

LEASE: Feik #5

COMPLETED: August 15, 1963

LOCATION: CS/2 NW NE
Sec. 4-26S-2E
Sedgwick County, Ks.

TOTAL DEPTH: 2912'

CONTRACTOR: Canaday Drilling Co.
6427 East Kellogg
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1963

CASING: 150' of 8 5/8" w/130 sacks 2% C.C.

CONSERVATION DIVISION
Wichita, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

230	Lime w/Shale	2330	Lime & Shale
525	Lime & Shale	2490	Shale w/Lime
825	Shale & Shells	2595	Lime - Shale
1540	Shale - Lime	2907	Shale - Lime
1840	Shale & Shells	2912	Sand
2010	Shale w/Lime	2912	T.D.

I, Granville E. Canaday, Jr. of
CANADAY DRILLING COMPANY certify
the above Well Log to be true to
the best of my knowledge.

Granville E. Canaday, Jr.

Subscribed and sworn to before me, a Notary Public in and for Sedgwick
County, Kansas this 15th day of August, 1963.

My Commission Expires Jan. 31, 1967

Pat Seashore
Notary Public