


15-173-01918-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Sedgwick County. Sec. 2 Twp. 26 Rge. 2 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE SW  
Lease Owner Sohio Petroleum Company  
Lease Name Penner Well No. 1  
Office Address Box 673, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed May 19 50  
Application for plugging filed 8-13-51 19  
Application for plugging approved 8-15-51 19  
Plugging commenced 9-1-51 19  
Plugging completed 9-1-51 19  
Reason for abandonment of well or producing formation Well depleted to a point uneconomical of production  
If a producing well is abandoned, date of last production 9-11-50 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilley  
Producing formation Mississippi Chat Depth to top 2283' Bottom 2287' Total Depth of Well 2287' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Chat	Oil	2283	2287	5 $\frac{1}{2}$ "	2280'	2292'
					Prob 2280'	Good

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 150'. Put in rock bridge and cemented with 15 sacks to 105'. Mud to bottom of cellar and capped with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Frank Carrol  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
J. H. Bond (employee of owner) or (owner/operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 19 51

My Commission Expires July 2, 1953  
My commission expires \_\_\_\_\_  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
PLUGGING  
FILE SEC 2 TWP 26 RGE 2  
BOOK PAGE 103 LINE 8

C O P Y

LOCATION: Penner #1  
NW-SE-SW Sec. 2-26S-2E  
Sedgwick County, Kansas

COMPANY: Sohio Petroleum Company

Contractor: Eckland Drilling Co.

Casing: 155' 8 5/8"

Commenced: 5-3-50

Cement: 100 sacks cement

Completed: 5-13-50

ROTARY DEPTH: 2887

---

30	surface clay
45	sand and gravel
65	shale
90	shale and shells
100	shale and shells
105	shale
125	lime
150	shale and lime
155	lime and shale
165	lime
210	lime and shale
380	lime and shale
395	lime and shale
400	sand
510	lime and shale
570	shale and shells
573	red rock
755	lime and shale
800	lime and shale
1125	shale and shells
1310	shale and shells
1550	shale and shells
1595	shale and shells
1715	shale and lime
1860	lime and shale
2018	lime and shale
2125	lime and shale
2222	lime and shale
2307	lime and shale
2400	lime and shale
2442	lime and shale
2490	lime
2560	lime and shale (brks.)
2600	lime and shale
2640	shale
2765	shale and lime
2860	shale and lime
2862	shale and lime
2880	lime and chert

