

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

SEDGWICK

County, Sec. 1 Twp. 26 Rge. 2 (E) ~~XXX~~

Location as "NE/CNW/SW" or footage from lines SE of SW of NE

Lease Owner Aurora Gasoline Company

Lease Name Berkschinger

Well No. 1

Office Address 802 Union National Bank Bldg, Wichita

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 5-11-56 19

Application for plugging filed 5-11-56 19

Application for plugging approved 5-11-56 19

Plugging commenced 5-11-56 19

Plugging completed 5-11-56 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Mississippian Depth to top _____ Bottom 2875 Total Depth of Well 2875 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	102	8-5/8	102	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2875 to 100 Fill w/heavy mud
100 Good permanent plug plus 1/2 sax hulls plus
15 sax cement thru 3 jts drill pipe
25' good permanent plug plus 1/2 sax hulls and
10 sax cement to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James Armour (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour James Armour
817 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of May, 19 56

My commission expires December 29, 1959

Marjorie Hall
Marjorie Hall Notary Public.

PLUGGING
FILE SEC. 1 T. 26 R. 2E
BOOK PAGE 61 LINE 37

5-19-56
Wichita, Kansas

DRILLING LOG

COMPANY: Aurora Gasline Company
CONTRACTOR: Shaver-Armour, Inc.
WELL NAME: BERESCHINSKI #1
COMMENCED: May 4, 1956
COMPLETED: May 11, 1956

Location: NE of SW of NE
Section 1-26-2E
Sedgwick County
Elevation: GE 1946
IF 1950
MB 1953

102' GASLINE REQUIRED
8-5/8" w/85 psi/cm

FORMATION

TO

Surface hole	102		
Anhydrite & Shale	200		
Line w/Shale Stks	300		
Line	400		
Line & Shale	455		TOPS
Shale	1000		
Shale & Line Stks	1315	Kansas City	2372
Shale & Line	1700	Mississippi	2800
Shale Line Shells	2010	Misc Chert	2818
Line & Shale	2105		
Line w/Shale Stks	2205		
Line & Shale	2830		
Misc. Line	2845		
Misc. Hole	2850		
Misc. Chert LTD	2875		

2372
1353
1019

STATE OF KANSAS)
SEWICK COUNTY) ss

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

Shaver-Armour, Inc.

By: James Armour
James Armour, Son, Trust.

Subscribed and sworn to before me this 17th day of May 1956

Marjorie Hall
Marjorie Hall, Notary Public

My commission expires December 29, 1959

PLUGGING
FILE SEC. 1 T 26 R 2E
BOOK PAGE 61 LINE 37