


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sedgwick County, Sec. 1 Twp. 26 Rge. 2E (E) (W)
Location as "NE/CNWSW" or footage from lines SE NE SW
Lease Owner Edgecomb, Inc.
Lease Name Elliott #3 Well No.
Office Address McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/23/73 19
Plugging completed 5/25/75 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dewey
Producing formation Depth to top Bottom Total Depth of Well 2871 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	120	none
				5 1/2"	2870'	1958'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 2871', plugged off bottom with 5 sacks cement.
Shot pipe at 2149', 1950', pulled 60 joints. Set 10' rock bridge
at 235', ran 20 sacks cement. Capped well with 10 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1973
6-4-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 30th day of May, 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- AURORA GASOLINE COMPANY,
Farm- Elliott No. 3

SEC. 1 T. 26 R. 2E
SE NE SW

Total Depth. 2871'
Comm. 7-15-57 Comp. 7-24-57
Shot or Treated.
Contractor. Veeder Supply & Development Co.
Issued. 10-19-57

County Sedgwick
KANSAS



Elevation. 1334 RB

Production. 25 BOPD

CASING:

8 5/8" 120' cem. w/80 sx
5 1/2" 2871' cem. w/100 sx

Figures indicate Bottom of Formations.

sod	15
lime & shale streaks	90
lime & shale	110
lime	200
lime, shale streaks	575
lime	755
lime & shale	825
shale w/lime streaks	1022
shale & lime	1660
lime	1705
shale & lime	1720
lime & shale	1860
shale & lime	2078
shale w/lime streaks	2192
lime & shale	2450
lime	2482
lime K.C.	2530
shale & lime	2650
shale & shells	2706
shale & lime	2790
lime & chert, Mississippi	2813
Mississippi lime	2855
lime & chert	2871
Total Depth	

Tops: Scouts	
Lansing	2126
Kansas City	2349
Erosional Mississippi	2780
Mississippi Lime	2817

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1972
CONSERVATION DIVISION
Wichita, Kansas