

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-173-20, 7/4-00
00

LEASE NAME Elliot

WELL NUMBER #1

SPOT LOCATION 590 Fron, FSL

SEC. 1 TWP. 26 RGE. 2 (X) or (Y)

COUNTY SG

Date Well Completed 1-8-86

Plugging Commenced 3-11-88

Plugging Completed 3-14-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Midco Energy Inc.

ADDRESS P.O. Box 781025 Wichita, Ks

PHONE (316) 681-0295 OPERATORS LICENSE NO. 3710

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, is well log attached? N/A

Producing formation Keokuk Depth to top 2512 bottom 2847 T.D. 2879

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Keokuk</u>				<u>4 1/2</u>	<u>2879</u>	<u>2332</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. dropped rock to 50' above perfs. topped w/ 4 sacks of cement.
Top plug set at 70' below surface dropped rock to 50' below surface, and filled w/ ready mix to top - total 263'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jonathan Oil Co.
Address 804 N. Haverhill, Eldorado, Ks 67042

License No. 11231
STATE CORPORATION COMMISSION
9-16-88
SEP 16 1988


STATE OF KANSAS COUNTY OF Butler, ss.

R. L. KRENBIEG (employee of operator) of

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. L. Krebief

(Address) Wichita



SUBSCRIBED AND SWORN TO before me this 14th day of Sept, 19 88

Marietta Brown
Notary Public

My Commission expires: 9/19/90

PORT BOLIVAR NATURAL
RESOURCES CORPORATION
P. O. BOX 11732
WICHITA, KS. 67202

#1 ELLIOTT

1-26-2E
590'FSL &
750'FWL, SW 1/4

CONTR RED TIGER DRILLING CTY SEDGWICK
GEOL L. E. CARTER FIELD GREENWICH

+	+	+
+	+	+
+	+	+

ELV 1357 KB SPD 1/3/86 CARD 1/8/87 IP TEMP ABD
1352 GL DRLG COMP 1/8/86
API 15-173-20,714

SMP	Top	Depth/Datum
LANS		2072-- 715
PLATTSBG		2201-- 844
BONN SPR		2249-- 892
CHANUTE		2317-- 960
DRUM		2387--1030
STARK		2496--1139
HUSH		2525--1168
CHER SH		2803--1446
MISS		2819--1462
SPERGEN		2839--1482
WARSAW		2851--1494
KEOKUK		2875--1518
RTD		2879--1522

8 5/8 " 213 / 185 SX, 4 1/2 " 2513 / 100 SX
FR SO IN SWOPE LM (SOME FREE OIL, PORO 14%)
SO IN HERTHA LM (UPR 2' GD SO BTM 3' - STN ONLY PORO
13-21%)
FR-GSO IN MISS FROM 2832-2833 (SUCR. GD ODOR BRN YLLW
FLUOR, SOME FREE OIL, PORO 10%)
GSO IN SPERGEN CHTY DOL FROM 2839-2844 (FR-GSO SOME
FREE OIL, PORO 27%)
FAINT ODOR IN KEOKUK CHT FROM 2876-2879 (FR SO SCATT
YLLW FLUOR, STN OIL WHEN CRUSHED, SCATT SMALL D
BRWN OIL GLOBULES)
NO CORES
DST (1) 2842-2879 (SPERGEN) / 30-30-90-60, REC 310 G &
OCM (15% G, 2% OIL, 83% M), 248' G & OCWM (20% G, 1%
OIL, 70% M, 9% W), 186' WTR, SIP 578-589#, FP 71-76 161-
225#, HP 1500-1500#
NOTE: CORRECTION: 1/21/86 - ORIGINALLY FIRST REPORTED IN
600'FSL & 800'FWL, SW 1/4

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

PORT BOLIVAR NATURAL
RESOURCES CORPORATION #1 ELLIOTT

1-26-2E
590'FSL &
750'FWL, SW 1/4

MIC - CO, PF (MISS) 2828-2837 & 2844-2847, W / 3 SPF, AC 300 GAL (28%), FU 100' FL (80' OIL & 20' AC
WTR), RE-AC 400 GAL (28% NE) & 30 GAL ANADALL, SWB LD, FU 425' FL (150' OIL ON TOP), RE-AC 100 GAL
(10% MCA), FRAC 200 BBL GEL SW & 2600# SD, SWB PT LD, SION, 300' GIP, FU 250' FL (10% OIL), SWB 8
BFPH (10% OIL), ONFU 1300' FL (10% OIL), PROD DECL TO 3 BFPH, NON-COMMERCIAL, RE-PF (MISS)
2844.5-2848.5, W / 3 SPF, AC 500 GAL (15% HCL), SWB LD, NON-COMMERCIAL, RE-PF (MISS) 2840-2844,
2828-2847, W / 3 SPF, NON-COMMERCIAL, SET CIBP AT 2573, PF (KC) 2504-2510, W / 2 SPF, AC 500 GAL
(15% HCL), SWB LD, NON-COMMERCIAL, PF (SWOPE) 2512-2517, W / 3 SPF, SWB D'WN, NAT, NON-COM-
MERCIAL, TEMP ABD 9/11/86, TO RETEST MISS AT A LATER DATE - NO OTHER INFO TO BE RELEASED AT PRE-
SENT - WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP 1/8/87

STATE CORPORATION COMMISSION

FEB 29 1988

CONSERVATION DIVISION
Wichita, Kansas