

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00150-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 22-17

LOCATION NE NE SE

SEC. 18 TWP. 8 RGE 21

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Calhoun Box 359

Operator Peel * Hardman Address Hoisington, Kans

Field _____ County Graham

Total Depth 3630 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 220' circulated with cement - 5 1/2" at 3530' 3594'
with 100 sax cement behind.

Filled with chat to 3625', set 4 sax cement with dump bailer,
pulled 2840' 5 1/8", filled hole with heavy mud to 215', set
rock bridge and 15 sax cement, filled with heavy mud to
40' set rock bridge and 10 sax cement to bottom cellar.

9-23-50

PLUGGING
FILE SEC 18 T 8 R 21W
BOOK PAGE 22 LINE 17

[Signature]
District Conservation Agent

Date 9-21-50