

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
Rev. 6-26-62

RECEIVED  
OCT 8 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-065-30149-00-00

10-3-66

Operator's Full Name J. M. Stewart.

Complete Address: 608 Union Center, Wichita, Kansas.

Lease Name Newell Estate Well No. 1

Location CS/2-S/2-SE/4 Sec. 36 Twp. 8 Rge. (E) (W) 21

County Graham Total Depth 3670

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gabbert and Jones, Incorporated,

Address: 514 Orpheum Building, Wichita, Kansas. License No.     

Operation Completed: Hour 5:30AM Day 28 Month 9 Year 1966

The Above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 160 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 10/3/66  
INV. NO. 4028-W