

KANSAS

Form CP-3  
Rev. 6-4-68

*2*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1973  
Mar 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name K & E Drilling, Incorporated,  
 Complete Address 816 Union Center, Wichita, Kansas.  
 Lease Name Stuchlik Well No. 1  
 Location CNE-NE Sec. 7 Twp. 8 Rge. (E) (W) 22  
 County Graham Total Depth 3660'  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated \_\_\_\_\_  
 Plugging Contractor Halliburton Services,  
 Address Box #296, Hill City, Kansas. License No. \_\_\_\_\_  
 Operation Completed: Hour 2:45 PM Day 1 Month 3 Year 1973

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 250 Sx.  
3659'--4 1/2" Production casing cemented on bottom with 125 Sx., DV Tool set @ 1890'  
with Chem-Pak. Well plugged back to 3200'. 4 1/2" casing has been squeezed in the  
Cedar Hills three separate times.

Attempted to pump into annulus was unable to do so. Squeezed 4 1/2" casing with 175  
Cu. Ft. 50/50 Pozmix 6% gel. Pump-in pressure 500#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 3/7/73  
INV. NO. 9104-U