

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 - 1972
MAY 4 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Landes Exploration Company,
Complete Address Box #867, Magnolia, Arkansas.
Lease Name Casey Jones Well No. 1
Location SW-NW-SW Sec. 7 Twp. 8 Rge. (E) (W) 22
County Graham Total Depth 3486'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Hellar Drilling Company, Incorporated,
Address 339 Union Center, Wichita, Ks. License No.
Operation Completed: Hour 10:00 PM Day 1 Month 5 Year 1972

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 550'.

Circulated hole with heavy mud. Pulled DP to 775' and displaced 110 Cu. Ft. cement
thru DP from 775' to 450'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/8/72
INV. NO. 5685-W

Signed: K. L. Driskell
Well Plugging Supervisor