

76
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1965
MAR 19, 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address: 410 4th National Bank Building, Wichita, Kansas.

Lease Name Alexander Well No. 1

Location CSW-SE Sec. 7 Twp. 8 Rge. (E) (W)22

County Graham Total Depth 3630

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: D & D Drilling Company, Incorporated,

Address: 307 Schweiter Building, Wichita, Kansas License No.

Operation Completed: Hour 10:30PM Day 14 Month 3 Year 1965

The Above well was plugged as follows:

218'--9" Surface pipe, cement circulated with 185 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-

placed 20 Sx, cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx, cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 3/19/65

INV. NO. 843-W

Signed: A. L. Dechub
Well Plugging Supervisor