

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: SW SE SE Sec. 8 Twp. 8 Rge. _____ (E) _____ (W) 22

Name of Field: _____ Total Depth: 3524

I have this date completed supervision of plugging of:

Lease Name: Schnebly Well No. 2

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Cenger Wichita, Kansas

Plugging Contractor: same & Sun Cementing Co

Address: _____ License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4:30PM Day 25 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 177' circulated with cement - 5 1/2" 3515' with 50 sax cement.

Filled with sand to 3500', set 5 sax cement with dump bailer, pulled

3100' 5 1/2" to 450', circulated hole with heavy mud (40 sax Gel), displaced

20 sax cement through 5 1/2" at 450', heavy mud to 175', displaced 20 sax

cement through 5 1/2", heavy mud to 30', set bridge and filled to bottom

cellar with cement.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

RECEIVED INVOICED
STATE CORPORATION COMMISSION
AUG 1 1961
AUG 1 1961 DATE 8/9/61
CONSERVATION DIVISION 3554-W
Wichita, Kansas