



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-26719-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
11-4-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Martin Explorations,

Complete Address 527 Union Center, Wichita, Kansas.

Lease Name Sayers Well No. 1

Location CSE-NE Sec. 10 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 11:00 AM Day 28 Month 10 Year 1974

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displced 110 Cu. Ft. cement
thru DP from 1075' to 750'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Daniels
Well Plugging Supervisor

INVOICED
DATE 11/4/74
INV. NO. 245-W