



15-065-20262-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1969
CONSERVATION DIVISION
Wichita, Kansas

9-29-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Roy Cook of Imperial Oil Company, has this
date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Fink Well No. C-1

Location: CSE-NE, Sec. 21 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent