

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20228-00-00

06-02-1969
 RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Gosselin Well No. A-1

Location: NE-SE Sec. 24 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3695' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 600'.

Circulate hole with heavy mud. Pull DP to 800' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent