



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-065-20220-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. F. R. Holt of Shields Oil Producers, Inc., has this date requested permission to plug the following described well:

Mr. Holt guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Smith Estate Well No. A-1

Location: NW-NW-SE Sec. 23 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3740' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Holt was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.

3630'--5 1/2" Production casing cemented on bottom with 75 Sx. Plugged back to 3619'. Top perforations from 3580' to 3584'. Top of cement @ 3150'. (Temperature Survey).

Sand well back to 3525' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx. cement, staged.

Very truly yours,

M. L. Dickels
Conservation Division Agent