



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-065-02696-00-01

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

OCT 28 1963
 10-28-1963
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Inc. has this

date requested permission to plug the following described well:

John C. Farmer Inc.

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: John C. Farmer, Inc.,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Benoit Well No. 1

Location: SE-SE-NW Sec. 24 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3748 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Comstock was instructed to plug the well as follows:

156'---3 5/8" Surface pipe, cement circulated.
3747'---4 1/2", cemented with 100 Sx. Plugged back to 3460',
Top perforations @ 3426'. Top of cement @ 3370' (Temp Survey).

Sand well back to 3410' and 2 Sx cement with dump bailer.
Pull 4 1/2" to 600', circulate heavy gel mud and displace 20 Sx
cement thru 4 1/2". Pull 4 1/2" to 150' and displace 20 Sx cement
thru 4 1/2". Pull 4 1/2" set bridge @ 35' and 10 Sx cement to
bottom of cellar.

Very truly yours,

H. L. Nichol
 Conservation Division Agent