

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas
may 24, 1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Isadore Dreher of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Dreher guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Mickelson Well No. A-1

Location: NW-NW-SE Sec. 27 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3775' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dreher was instructed to plug the well as follows:

165'--8 5/8" Surface casing, cement circulated.
3762'--5 1/2" Production casing cemented on bottom. No plug back nor perforations indicated.

Push plug to 3300', sand back to 3275' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 15 sacks gel and 150 Sx. cement, staged.

Very truly yours,

R. S. Nichols
Conservation Division Agent