

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1971

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Isadore Dreher of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Dreher guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Mickelson Well No. C-1

Location: SE-SW-NE Sec. 27 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3785' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dreher was instructed to plug the well as follows:

165'--8 5/8" Surface casing, cement circulated.
3761'--5 1/2" Production casing cemented on bottom. Well plugged back to
3580'. Top perforations @ 3502'.

Sand back to 3490' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 15 sacks gel and 150 Sx.
cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent