

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 24 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 5-24-1971

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Isadore Dreher of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Dreher guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Mickelson Well No. C-2

Location: NW-SE-NE Sec. 27 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3797' Oil Well

Gas Well  Input Well  SWD Well X D & A  Lost Hole

Mr. Dreher was instructed to plug the well as follows:

165'--8 5/8" Surface casing cement circulated.  
3715'--5 1/2" casing cemented on bottom. No plug back indicated, Top perforations @ 3504'. No attempt to salvage 5 1/2" casing.

Squeeze 5 1/2" casing with 1 sack hulls, 25 sacks gel and 100 Sx. cement, staged. Squeeze annulus with 150 Sx. cement.

Very truly yours,

M. L. Nichols  
 Conservation Division Agent