

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
May 24, 1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Isadore Dreher of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Dreher guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Mickelson Well No. C-3

Location: N/2-SW-NE Sec. 27 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3768' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Dreher was instructed to plug the well as follows:

165'--8 5/8" surface casing, cement circulated.  
3684'--5 1/2" Production casing cemented on bottom. Well plugged back to 3500'  
Top perforations @ 3472'.

Push plug to 3300' sand back to 3275' and set 5 Sx. cement with dump  
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 15 sacks  
gel and 150 Sx. cement, staged.

Very truly yours,

*H. S. Nichols*  
Conservation Division Agent