

15-065-20240-00-00

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
July 18<sup>th</sup>, 1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Burkhart of Sage Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Burkhart guarantees payment of the plugging fee.

Operator's full Name: Herndon Drilling Company,

Complete Address: P. O. Box #489, Tulsa, Oklahoma.

Lease Name: Pembleton Well No. 1

Location: GS/2-S/2-SW/4 Sec. 2 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3730' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burkhart was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated with 175 Sx.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.

cement thru DP. Pull DP to 250' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom

of cellar.

Very truly yours,

Conservation Division Agent