



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 27 1963  
 3-27-63  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co. has this

date requested permission to plug the following described well:  
Murfin Drilling Co.

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Co,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Johnson Well No. 1

Location: SE-SE-SE Sec. 4 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3770 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Hoberecht was instructed to plug the well as follows:

280'-85/8" surface pipe cement circulated w/150 Sx.  
3768' 5 1/2" production casing cemented w/100 Sx. Well plugged  
back to 3740'. Top of perforations @ 3706'

Sand well back to 3690' and set 5 Sx cement w/dump bailer.  
Pull 5 1/2" to 550', circulate heavy gel mud and displace 20 Sx  
cement thru 5 1/2". Pull casing to 270' and displace 20 Sx  
cement thru 5 1/2". Pull casing set bridge @ 35' and 10 Sx  
cement to bottom of cellar.

Very truly yours,

H. A. Nichols  
 Conservation Division Agent