



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Clark Well No. 1

Location: CNWONW Sec. 5 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3170' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 250' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent