

6 070495

Nov-12-24-48

197R

API NUMBER 15-163-01421-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE-SE-NE, SEC. 23, T. 8 S, R. 19

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015
Operator: Heller Drilling Co. Inc.
Name & Address: 711 Petroleum Bldg
Wichita, Kans. 67202
Carl Gilpin

Lease Name LOWRY Well # 2
County Rooks 111.12
Well Total Depth 3419 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 10 3/4 feet 157

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address 24 South Lincoln, Box 31, Russell, Kans. 67665

Company to plug at: Hour: 1:00 PM Day: 18th Month: July Year: 19 86

Plugging proposal received from Carl Gilpin

(company name) Heller Drilling Co. Inc. (phone) 316-267-2845

were: 10 3/4" S.C. @ 157' m/150' ent, 7" Csg. S.C. @ 3416' m/100' ent,
5 1/2" liner. 0 to 1430' cemented to surface, 2 7/8" liner cemented
from 3325' to 2671' m/150' ent, Plug Back 3346', Perf. 3071 to
3344' well condition good - no leak. Proposal, Order 300 ^{SK} 6 5/35,
Pozmix Gel - ^{10%} additive, with pump truck, load and pressure m/cement
10 3/4", 7" and 5 1/2" csg. Plugging Proposal Received by M. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:00 PM Day: 18th Month: July Year: 19 86

ACTUAL PLUGGING REPORT

Ordered 300 ^{SK} 6 5/35 Pozmix 10% Gel - 2% Additive,
and 5 ^{SK} shells, Pumped in with pump truck.
1) Pumped 50 ^{SK} Cem in 10 3/4" S.P. m/1 ^{SK} shells, -> 300 Psi.g.
2) Pumped 50 ^{SK} Cem in 7" Csg m/1 ^{SK} shells, -> 500 Psi.g.
3. Pumped 200 ^{SK} Cem m/3 ^{SK} shells in 5" Csg, -> 400 Psi.g.
Cemented by Allied Cementing, Russell, 16

Remarks: _____
(If additional description is necessary, use BACK of this form)

RECEIVED

INVOICED did not observe this plugging.

DATE JUL 25 1986

INV. NO. 14515

Signed M. Schmidt 7-24-86
(TECHNICIAN)

JUL 25 1986 7/25/86

Carl Gilpin - Info. - 7-23-86

Lourey #3

- 1) Squeezed In 1955 $\frac{1}{150}$ SK @ 1220 ft
- 2) " " 9-12-62 $\frac{1}{175}$ SK @ 1170 ft.
- 3) " " 1967 Ran $5\frac{1}{2}$ " liner, Cemented
from 1430 to Surface.