

4-071194

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-16

API Number: 15-163-21,643-00-00

SW NE SW /4 SEC. 33, 08 S, 19 W
1650 feet from S section line
1650 feet from W section line

Operator license# 3456

Lease: Cerrow Well # 3

Operator: A.F.G. Energy, Inc.

County: Rooks 112.45

Address: P.O. Box 458
Hays, Kansas 67601
Terry Piesker

Well total depth 3460 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 263 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 16 Month: October Year: 1996

Plugging proposal received from: Terry Piesker

Company: A.F.G. Energy, Inc. Phone: 913-625-6374

Were: 8 5/8" - 263' S.P. w/170 sxs cmt. 5 1/2" casing set at 3453' w/100 sxs cement.
Anhy. 1427' - Elv. 2014' - P.B.T.D. 3448' - Arbuckle well. Proposal perf 5 1/2" casing at
2000' - 1437' - 840'. Order 350 sxs 60/40 pozmix - 8% gel and 5 sxs hulls. Pump in with
pump truck. Spot and displace all cement through tubing. Squeeze annulus with cement. Load
5 1/2" casing bottom to top with cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:30 P.M., Day: 16, Month: October, Year: 1996

Actual plugging report: A.F.G. Energy ordered 350 sxs 60/40 pozmix - 8% gel - 5 sxs hulls.
Pumped in with pump truck. Spotted and displace all cement through tubing.

- 1) Perforated 5 1/2" casing at 2000' - 1437' - 840'.
- 2) 2 7/8" tubing at 3408' - spotted and displace with 100 sxs cement w/4 sxs hulls added.
- 3) 2 7/8" tubing at 2104' cwc with 130 sxs cement with 1 sack hulls - cement circulated.
- 4) Squeezed 5 1/2" casing with 50 sxs cement - Max. P.S.I. 200#.
- 5) Squeezed 5 1/2" x 8 5/8" annulus with approx. 35 sxs cement. Casing ruptured.
- 6) 10-25-96 AFG pressured 5 1/2" x 8 5/8" annulus. Did not take cement. Max. P.S.I. 500#.

S.I.P. 500#.

Remarks: Cemented by Allied Cement Company.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2014 GL

And did not observe the plugging.

Marion J. Schmidt
(agent)

INVOICED

DATE OCT 30 1996

INV. NO. 46863