

6-23 4-032312

15-163-23201-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: ~~15-051-24,820~~

C E2 NW SE /4 SEC. 33, 08, 19 W  
1980 feet from S section line  
1650 feet from E section line

Operator license# 30347  
Operator: Decab Company  
Address: 1202 Hickory  
Victoria, Kansas 67671

Lease: Amrein Well # 1  
County: Rooks 111.41  
Well total depth 3428 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: L&M Well Service License# 31172

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 23 Month: June Year: 1998

Plugging proposal received from: Arnie Michaelis

Company: L&M Well Service Phone: \_\_\_\_\_

Were: Order 200 sxs 60/40 pozmix - 10% gel - 400# hulls - 16 sxs gel.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 3:15 P.M., Day: 23 Month: June Year: 1998

Actual plugging report: 8 5/8" set at 262' w/150 sxs cwc. 5 1/2" set at 3438' w/375 sxs.  
BP over arbuckle at 3410'. Ran tubing to 3428' displaced 40 sxs cement blend with 200# hulls. Pulled to 3125' displaced 16 sxs gel. Pulled to 1450' displaced 100 sxs cement blend with 250# hulls. Backoff 5 1/2" casing. Pulled 5 1/2" casing and topped off 8 5/8" with 35 sxs cement blend. Plug complete. Recovered 30' of 5 1/2".

Remarks:  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did[ X ] / did not[ ] observe the plugging. Carl Goodrow  
(agent)

INVOICED

DATE 7-30-98

INV. NO. 51043

6-23 SEP 18 1998

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
7/28/98