

6 030782

15-163-01136-00-064
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA 0Wwo 1975

NWNWSW SEC. 34, T. 8 S, R. 19 WDB

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name CERROW Well # 1

Operator: STATE OF KANSAS AND

County Reeks

Name & Address PAUL H. WILLIAMS BANKRUPTCY

Well Total Depth 3391 feet

TRUSTEE

Conductor Pipe: Size _____ feet

Surface Casing: Size 10" feet 208'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor STATE OF KANSAS KCC License Number _____

Address WICHITA, KANSAS 67202

Company to plug at: Hour: PM Day: 21 Month: 8 Year: 19 86

Plugging proposal received from DUANE RANKIN DON BUTCHER & CARL GOODROW

(company name) CONS. DIV. OF KCC DIST. 6 HAYS (phone) _____

were: 10" SET @ 208' 7" SET @ 3389' THIS WAS A FLOWING WELL

RODS AND TUBING WERE STRIPPED FROM THE WELL AS THE PACKER AND BOTTOM WAS SANDED IN. THERE WERE HOLES IN THE TUBING AND CASING. IN THE CEDAR HILLS SECTION AND ELSEWHERE.

ORDERED 1400 SX. 60/40 P02 4 1/2 GEL 3 1/2 CC - 7 SX. HULLS ALLIED CEMENT COMPANY Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:45 PM Day: 21 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT THE WELL WAS PLUGGED BY PUMPING DOWN THE 2 7/8" TUBING WITH CEMENT SLURRY IN A SERIES OF PUMPING CEMENT SLURRY THEN LAYING DOWN A NUMBER OF JOINTS OF PIPE.

AS: MIX & PUMP 75 SX. CMT. MIX. + HULLS LAYDOWN 10 JOINTS MIX & PUMP 75 SX. CMT. MIX LAYDOWN 20 JOINTS MIX & PUMP 75 SX. CMT. MIX + HULLS LAYDOWN 20 JOINTS TUBING MIX & PUMP 100 SX. CMT. MIX. LAYDOWN REST OF TUBING

Remarks: TIE ON TO CASING (7") MIX. & PUMP 75 SX. CMT MIX. PRESSURED UP BLEW OFF HEAD CEMENT STAYED AT SURFACE PLUG. COMP.

I (did / did not) observe this plugging.

BACKSIDE DRY AND WOULD NOT TAKE FLUID. Signed Carl Goodrow (TECHNICIAN) 8-29-86

20 SEP 2 9/2/86 LWD