

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-01423-0000

SW SW NW, Sec. 34, T 8 S, R 19 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Veyerka Well # 1

Operator: Petroleum, Inc.
Name & Box 186
Address Palinville, Ks. 67663

County Rooks

Well Total Depth 3382 feet 109.92

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 250'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing and ABC Redi-mix License Number _____

Address Box 31 332 West Wichita, Russell, Kansas 67665

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Jay Mongeau

(company name) Petroleum, Inc. (phone) (913)434-4647

were: This well was plugged with pump truck, by Allied Cementing, on 12-12-83. Plugged
dropped 668'. Because of location and weather, plugging was delayed. Used Redi-mix to
fill csg to surface, March 16th, 1984. 8 5/8" 250' S.P. CUC w/125 sks, 5 1/2" csg set @ 3380'
w/150 sks cmt. Hole in csg at approximate 800 to 1000', ordered 250 sks 50/50 pozmix
6% gel 3% cal. cl., 18 sks gel 4 sks hull's and 5 1/2" plug, pumped in 5 1/2" csg and annulus
with pump truck.

Signed Marian J. Schmidt
DOTC (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 16th Month: March Year: 19 84

ACTUAL PLUGGING REPORT Ordered on 12-21-83. 250 sks 50/50 pozmix 6% gel 3% cal. cl.,
18 sks gel 4 sks hull's and 5 1/2" plug. Pumped in annulus, 100 sks cmt. max pressure
300 PSI. In 5 1/2" csg, Pumped in, 20 sks cmt., 30 sks cmt. w/3 sks hull's mixed in 18 sks
gel, Rel, plug and 100 sks cmt., no pressure. Cemented by Allied Cmt. on Dec. 12, 1983.

Remarks: Plugged dropped 668' in 5 1/2" casing, annulus remained full. Returned on March
16th filled csg to surface with 3 1/2 yds. redi-mix by ABC redi mix, Plainville, Ks.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 3-29-84
INV. NO. 0979
3-16
RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Marian J. Schmidt
DOTC (TECHNICIAN)

KCC/KDHE JOINT OIL/GAS REGULATORY OFFICE

15-163-01423-00-28

DATE March 16, 1984

[] New Situation
[] Response to Request
[X] Follow-up

OPERATOR Petroleum Inc. # 5238

NAME Petroleum Inc.

LOCATION SW SW NW, SEC 34, T 8 S, R 19 W

& ADDRESS Box 186, Plainville, Kansas

LEASE Veyerka Well # 1

PHONE NO. _____
OPER. _____ OTHER _____

COUNTY Rooks

REASON FOR INVESTIGATION: Returned on March 16, 1984. To fill casing to surface on the above previously plugged well, where plug had dropped 668' in 5 1/2" casing.

LEASE INSPECTION

PROBLEM: Plug in 5 1/2" casing dropped 668'

PERSON(S) CONTACTED: Jay Mongeau, Petroleum Inc.

FINDINGS: Filled 5 1/2" casing to surface with 3 1/2 yards of Redi-mix, by ABC Redi-mix cement Plainville, Kansas. Witnessed entire procedure. Completed @ 2:30 PM March 16, 1984

COMPLAINT

ACTION/RECOMMENDATIONS: None photos taken: _____

FIELD REPORT

Retain 1 copy Joint District Office
Send 1 copy Conservation Division
Send 1 copy KDHE/Topeka if appropriate

RECEIVED
STATE CORPORATION COMMISSION
By M. J. Schmidt ✓
DOIC District #6
MAR 26 1984
3/26/84
CONSERVATION