

6 030783

15-163-19163-0001/63

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA OWWO 1985

S(WNW) SEC. 34, T B S, R 19 (W)E

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name CERROW Well # 2 SWO

Operator: STATE OF KANSAS AND

County ROOKS

Name & Address BANKRUPTCY TRUSTEE

Well Total Depth 1607 feet

FOR PAUL WILLIAMS

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 239'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor STATE OF KANSAS KCC License Number _____

Address WICHITA, KANSAS 67202

Company to plug at: Hour: AM Day: 25 Month: 8 Year: 19 86

Plugging proposal received from DUANERANKIN DON BUTCHER CARL GOODROW

(company name) KCC CON. DIV. DIST #6 HAYS (phone) _____

were: 8 5/8" SET @ 239' 4 1/2" SET @ 1607' PERFORATED 828'-30' 1044'-54'

1090'-1098' 4/MT. RELEASE AND PULL PACKER AND 26 JOINTS OF 2"

PLASTIC LINED TUBING. 8 5/8" - 4 1/2" ANNULUS CEMENTED FROM 1607'

TO SURFACE w/ 650 SX. CEMENT ORDER 150 SX. 60/4002 4 1/2" 3 1/2" CC

5 SX. HULLS ALLIED CEMENT CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:45AM Day: 25 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT TIE ON TO 4 1/2" CSG. w/ SWEDGE MIX & Pump 50 SX.

(10 bbl) CEMENT MIX. SLURRY. Follow w/ 100 SX. (20 bbl) CEMENT MIX

SLURRY w/ 5 SX. HULLS ADDED IN. MAX. PSI LOCKED UP @ 1000* HELD

FOR 10 MIN. RELEASED TO 300* PSI HELD FOR 30 MIN. RELEASED

PRESSURE REMOVED SWEDGE AND HAD WELDER CUT OFF HEAD

BELOW 8 5/8" COLLAR @ BASE OF CELLAR WELDED ON 4 1/2" PLATE

Remarks: CEMENT WAS @ TOP OF 4 1/2" CSG. PLUG COMPLETE.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

8-29-86