

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20749-00-01  
Spot: W2W2NE Sec/Twnshp/Rge: 26-8S-18W  
3840 feet from S Section Line, 2240 feet from E Section Line  
Lease/Unit Name: P DECHANT Well Number: 2  
County: ROOKS Total Vertical Depth: 3478 feet

Operator License No.: 31824  
Op Name: BROWN, THOMAS M.  
Address: 403 NW 3RD PO BOX 250  
PLAINVILLE, KS 67663

Production Casing Size: 5.5 feet: 3424 130 SX CMT 8/13.04  
Surface Casing Size: 8.625 feet: 172 125 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/04/2003 9:00 AM  
Plug Co. License No.: 31824 Plug Co. Name: BROWN, THOMAS M.  
Proposal Rcvd. from: THOMAS M. BROWN Company: BROWN, THOMAS M. Phone: (785) 434-7141

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
T.O.F. at 1600'.  
Casing leak at 1000' and 1300'+.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/04/2003 12:00 PM KCC Agent: DENNIS HAMEL

**Actual Plugging Report:**

R.I.H. with tubing to 1590'.  
Rigged up cementers - pumped 100 sxs cement with 300# hulls - cement circulated at surface.  
POOH with tubing. Squeezed 100 sxs cement with 100# hulls.  
Max. P.S.I. 500#. S.I.P. 400#.  
Rigged up cementers to 8 5/8" S.P. - squeezed 30 sxs cement with 100# hulls.  
Max. P.S.I. 400#. S.I.P. 300#.

RECEIVED  
FEB 12 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 2-13-03  
INV. NO. 2003061191


FEB 10 2003

THE GENE BROWN COMPANY 26-8-18W  
 407 S. MAIN #2 P. DECHANT 'OWWO' 1440' FEN &  
 PLATVILLE, KS 67663 2200' FEL, NE/4  
 CONTR MURFIN DRILLING COMPANY CTY ROOKS

GEOLOGICAL FIELD DOPITA WEST

ELV 1978 KB SPD 4/20/83 CARD ISSUED 5/26/83 IP P 20 BO & 80 BWPD

API 15-163-20,749-A LKC 3144-3365 OA



LOG	Tops	Depth/Datum
ANH		1310-668
B/ANH		1347-631
TOP		2892-914
HEEB		3101-1123
TOR		3124-1146
LKC		3143-1165
BKC		3369-1391
CONG		3405-1427
RTD		3482-1504

OLD INFO: OPERATOR WAS MURFIN DRILLING COMPANY, #2 DECHANT SPD 10/19/77, SET 8 5/8" 172/125 SX COMP AS D&A/CONG 10/26/77 (CARD ISSUED 11/10/77) CONTR: COMPANY TOOLS; GEOL: ROGER WELTY; NO LOG  
 DST (1) 3122-3150 (TOR, LKC) 7 45-45-45-45, REC 65' HOCM & TR FO, SIP 412-298#, FP 22-57#, BHT 119'  
 DST (2) 3207-3234 (LKC) 7 45-45-45-45, REC 200' SOCMW, SIP 435-435#, FP 45-121#, BHT 121'  
 DST (3) 3301-3360 (LKC) 7 45-45-45-45, REC 120' M, SIP 797-774#, FP 45-91#  
 NEW INFO: FR 3/28/83, RE-ENTERED 4/20/83, WSH DWN TO RTD, LOGGED, SET 5 1/2" 3424/130SX, MICT - CO, PF (LKC) 3362-65, 3339-41, 3316-19, AC 1500G (15%) & 250# BENZ PLUGS; SWB DWN, GSO, PF (LKC) 3312-14, SWB DWN, SO, NAT, PF (LKC) 3229-32, AC 1000G (15%), SWB DWN, GSO, PF (LKC) 3184-87, AC 500G (15%), SWB DWN, GSO, PF (LKC) 3144-47, AC 500G (15%), SWB DWN, SO, RE-AC 2000G (28% RETD), SWB DWN, GSO, POP, P 20 BO & 80 BWPD (GR 37%), 5/10/83

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS