

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 856-00-00

TECHNICIAN'S PLUGGING REPORT

2970 feet from N S section line

990 feet from W E section line

Operator License # 7211

Lease Name HENYON HARDMAN Well # 2

Operator: L. F. A. OIL COMPANY
Name & Address: BOX 204
BOGUE, MANUS
67625

County GRAHAM

Well Total Depth 3566 feet \$115.90

Conductor Pipe: Size 6 feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BIG SPRINGS DRILL CO. License Number 5381

Address BOX 8287 MUNGER STATION, WICHITA, MANUS. 67208

Company to plug at: Hour: 12:00 PM Day: 14th Month: SEPT. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO STEVE BASYE

(company name) BIG SPRINGS DRILL, INC. (phone) 316-681-1723

were: 8 5/8" - 247 FT SR. CML #175 SK CMT. COMMON-2% GEL, 3% CA-CL. (ALLIED) BY

ORDER 200 SK 20/50 FORMIX 6% GEL, 3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.

FRIBUCKLE 3558 FT, ANHY. 1220 FT, ELV. 2025 FT

Signed [Signature]
(TECHNICIAN) 001C

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:00 PM Day: 14th Month: SEPT. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED - 200 SK 20/50 FORMIX 6% GEL, 3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER, MUD BETWEEN ALL PLUGS.

1st PLUG @ 3540 FT #20 SK CMT., 2nd PLUG @ 1230 FT #20 SK CMT.

3rd PLUG @ 810 FT #100 SK CMT., 4th PLUG @ 270 FT #40 SK CMT.

5th PLUG HULL'S-PLUG @ 40 FT #0 #10 SK CMT., 10 SK RHT HOLE (CIRCULATE)

Remarks: CEMENTED BY

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1983
CONSERVATION DIVISION
Wichita, Kansas
9-26-83

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 10-7-83

INV. NO. 5658-W

Signed [Signature]
(TECHNICIAN) 001C