

12-4-87

6 031010

065-22,095 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE SE NW SEC. 7, T 8 S, R 21 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4077

Lease Name W. Kenyon Well # 1

Operator: Kenyon-Hardman Oil Company
Name &
Address 3021 Claflin
Manhattan, Kansas 66502

County Graham 116.29

Well Total Depth 3578 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Russell, Kansas

Company to plug at: Hour: PM Day: 4 Month: Dec. Year: 19 87

Plugging proposal received from Blain Hardman

(company name) Kenyon - Hardman (phone) _____

were: 8 5/8" set at 252' cwc 175 sks. 5 1/2" set at 3576' w/825 sks D.V.

tool set at 1592'. cwc. Order 150 sks A.T.L. Cement Blend 65/35 Poz 10% Gel 2% Dical
5 sks Hulls. Allied Cement Co. Murfin Drilling Co. Water Truck

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 PM Day: 4 Month: Dec. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/150 sks Cement Blend w/5 sks Hulls
mixed in to Max Psi 1750#. Close in Psi 1000# Test backside to 300#. Cement at
surface. Plug complete.

12-29-87

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-30-87

INV. NO. 19311

Signed Carl Goodrow *Carl Goodrow*
(TECHNICIAN)
Carl Goodrow