

6070295

API NUMBER 15-065-22,182-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C-E 1/2-NW-1/4 SEC. 8, T. 8 S, R. 21 W

1980 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7211

Lease Name IRBY VEMICH Well # 2

Operator: L. T. A. OIL COMPANY

County GRAHAM 116.35

Name & Address BOX 204

Well Total Depth 2580 feet

BOGUE, MANVS.

Conductor Pipe: Size 0 feet

67625

Surface Casing: Size 8 5/8" feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BIG SPRINGS DRILLING, INC License Number 5381 # 146.144

Address WICHITA, MANVS. 67208

Company to plug at: Hour: 12:00 PM Day: MAY Month: 2 ND Year: 19 85

Plugging proposal received from TERRY AUSTON

(company name) BIG SPRINGS DRILLING, INC (phone) 913-674-5650

were: 8 5/8" - 260 FT S.O. CUM 165 SK COMMON GEL-CA-CL, BY ALLIED OMT.

ORDER 200 SK 50/50 FORMIX GEL-CA-CL - 1 SK CELLO FLAKE AND 8 5/8" PLUG

SPOT WITH DRILL STEM, RECONDITION HOLE (VIS) HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, MUD CONDITION, WEIGHT 9.4, VISCOSITY 46

FLV. 2026, ANH, 1584, (CONGLOMERATE MUD.)

Plugging Proposal Received by [Signature] BOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:00 PM Day: 2 ND Month: MAY Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 200 SK 50/50 FORMIX GEL-CA-CL - 1 SK CELLO FLAKE, 8 5/8" PLUG.

SPOTTED WITH DRILL STEM, RECONDITIONED HOLE, HEAVY MUD BETWEEN ALL PLUGS

1st Plug @ 1560 FT / 20 SK CNT, 2nd Plug @ 810 FT / 100 SK 1 SK CELLO FLAKE

3rd Plug @ 270 FT / 50 SK CNT, 4th Plug @ 40 FT / 10 SK CNT

10 SK IN RAT HOLE (CIRCULATE) OPERATED BY ALLIED OMT.

STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

DATE 5-14-85

Signed [Signature] BOIC (TECHNICIAN)

INV. NO. 8125

JUN 6 1985