

4-071076

11-25

00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,731

SE SE SW /4 SEC. 09, 08 S, 21 W  
330 feet from S section line  
2500 feet from E section line

Operator license# 31336

Lease Billips well # 1

Operator: Oil Quest Resources, Inc.

County Graham

118.14

Address: 518 17th - #560  
Denver, Colorado 80202  
William D. Helton

Well total depth 3635 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 274 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Emphasis Drilling - Allied Cement License#     

Address: Russell, Kansas 67665 - Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 25 Month: November Year: 93

Plugging proposal received from: Larry Langhoffer

Company: Emphasis Drilling Phone: 303-893-1972

Were: 13 3/4 conductor @ 51' w/60 sxs. 60/40 pozmix - 3% c.c. - 2% gel  
8 5/8" - 274' S.P. cwc. w/160 sxs. 60/40 pozmix - 2% gel - 3% c.c. -  
By Allied Cement. Elv. @ 2017' - anhy. @ 1527' - arbuckle @ 3570'. No  
circ. problems - mud condition 52 vis. - 9.2 wt. - 8 water loss -  
chlorides 1000 ppm @ 3409'. Proposal 225 sxs. 60/40 pozmix - 6% gel -  
1 sx. flocele. Circulate hole - spot and displace all cement through  
drill pipe - heavy mud between all plugs. 25 sxs. cmt. @ 3531' - 25 sxs.  
cmt. @ 1530'-100 sxs. & 1 sx. F.C. @ 780'-40 sxs. @ 325'-10 sxs. @ 40'.  
15 sxs. in rathole (cir) - 10 sxs. in mousehole (cir)  
Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 10:00A.M., Day: 25, Month: November, Year: 93

Actual plugging report: Emphasis ordered 225 sxs. 60/40 pozmix - 6% gel -  
1 sx. flocele. Circulated hole - spotted and displaced all cement  
through drill pipe - heavy mud between all plugs.  
1st. plug @ 3531' w/25 sxs. cement.  
2nd. plug @ 1530' w/25 sxs. cement.  
3rd. plug @ 780' w/100 sxs. cement w/1 sx. F.C.  
4th. plug @ 325' w/40 sxs. cement. 15 sxs. rathole (cir)  
5th. plug @ 40' w/10 sxs. cement. 10 sxs. mousehole (cir)

Remarks: By: Allied Cement.  
Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING X, CASING     . Elevation: 2021 GL

RECEIVED

STATE CORPORATION COMMISSION

DEC 15 1993

I did      observe the plugging.

INVOICED

Marion J. Schmidt  
Agent) 12-15-93  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 12-15-93  
INV. NO. 39538