

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065 21333-00-00

NE, Sec. 12, T 8 S, R21 W/E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5906

Lease Name Bethell Well # 1

Operator: Petro-Gas Energies Inc.  
Name & 411 Farmers & Bankers Bldg.  
Address Wichita, Kansas 67202

County Graham

Well Total Depth 3489 feet 113.39

Conductor Pipe: Size feet

Surface Casing: Size 8<sup>5/8</sup> feet 257

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Pfeifer Well Service License Number 6968

Address Hill City, Kansas

Company to plug at: Hour: AM Day: 7 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Ron Salsman

(company name) Pfeifer Well Service (phone)

were: Bottom plug = 4 sks com. cem. - sand to 50' above perms. 4 sks com. cem.

Top Plug = Pump down 8<sup>5/8</sup>" with 3 sks. hulls - 36 sks. gel. 100 sks cem. mix -

4 sks. gel - 8<sup>5/8</sup>" plug - 70 sks. cem mix recovered 1100' of 4<sup>1/2</sup>" casing.

Cem. mix 50/50 poz, 6% gel, 3% cc

Signed Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:15 AM Day: 7 Month: February Year: 19 84

ACTUAL PLUGGING REPORT As above

Allied Cement Company

Max. pressure 800#

Shut in at 300#

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1984  
CONSERVATION DIVISION  
Wichita, Kansas

2-27-84

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Carl Goodnow  
(TECHNICIAN)

FORM CP-2/39  
Rev. 9-82

INVOICED

DATE 3-5-84

INV. NO. 0508

2-7