

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-21,687-00-00

NW, Sec. 15, T 8 S, R 21 W/E

1650 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

#6171  
Operator License # High Plains Oil

Lease Name Gaslain Well # 1

Operator: 29th & Vine  
Name &  
Address Hayes, Ks. 67601

County Graham

Well Total Depth 3615 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 254

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 624

Address P.O. Box 506, Russell, Ks. 67665

Company to plug at: Hour: 11:00PM Day: 15 Month: Oct Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Dan Lavinger

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: Ordered 180 sacks 50% permix - 4% bul - 3% lat. cl. & 8 5/8" plug. Spnt w/ drill stem w/ heavy mud between all plugs. 1st plug C 3615' w/ 20 sacks, 2nd plug C 1554' w/ 20 sacks, 3rd plug C 800' w/ 80 sacks, 4th plug C 300' w/ 40 sacks, 5th plug - solid bridge of balls + plug C 40' w/ 10 sacks. Circulate 10 sacks in rat hole.

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:00AM Day: 16 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 254' SP. cas. w/ 150 sacks common - 2% bul - 3% lat. cl.

Ordered 180 sacks 50% permix - 4% bul - 3% lat. cl. & 8 5/8" plug. Spnt w/ drill stem w/ heavy mud between all plugs. 1st plug C 3615' w/ 20 sacks, 2nd plug C 1554' w/ 20 sacks, 3rd plug C 800' w/ 80 sacks, 4th plug C 300' w/ 40 sacks, 5th plug C 40' solid bridge of balls + plug w/ 10 sacks. Circulated 10 sacks in rat hole.

Remarks: \_\_\_\_\_

STATE CORPORATION COMMISSION  
RECEIVED  
NOV 1 1982  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated and that I (did / did not) observe this plugging.

INVOICED

DATE 11-15-82

INV. NO. 1580-0

Signed [Signature]  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82