

7-2-87

6 030887

API NUMBER 15-005-21545-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S/2 W SE, SEC. 34, T 8 S, R 21W/E  
330 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6016

Lease Name ~~Talbert~~ Talbert Well # 1

Operator: Condor Energy Inc.

County Graham

Name & Address: Box 108

Well Total Depth 3646' feet

Great Bend, Kansas

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cmt. Co. License Number \_\_\_\_\_

Address Plainville, Kansas

Company to plug at: Hour: AM Day: 2 Month: June Year: 19 87

Plugging proposal received from Jim Davis

(company name) Condor Energy Inc. (phone) 316-792-1751

were: 8 5/8 set at 200', 4 1/2 at 3646

Order 200 sks ATL 65/35 Poz 10% Gel 2% Dixel 5 sks Hulls.

Allied Cmt. Co. Sun-downer Water Trucks.

D.V. Tool 1535 w/400 sks CWC.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 PM Day: 2 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Due to well being two staged through DV tool at 1535'

the 4 1/2" csg was not perforated as per new opinion on cased holes.

Cmt. Co. tied onto 4 1/2" csg. and squeezed with 175 sks cmt. Blend and 5 sks. Hulls

w/ Max Psi. 1000#. Close in at 750# Psi. Plug complete.

STATE CORPORATION COMMISSION

JUL 10 1987

7-10-87

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 6-15-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 17248