

6030525

API NUMBER 15-065-21,684-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SESESW, SEC. 34, T. 8 S, R. 21 WB

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name GUILLAUME Well # 1-34

Operator: MURFIN DRUG. CO.

County GRAHAM 121.72

Name & Address 250 N. WATER, STE. 300

Well Total Depth 3745 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 231

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON CMT CO. License Number \_\_\_\_\_

Address OBERLIN KANSAS

Company to plug at: Hour: PM Day: 25 Month: 7 Year: 19 85

Plugging proposal received from PAT CANADAY

(company name) MURFIN DRUG. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 231' w/ 150 SX. 4 1/2" SET @ 3744' w/ 225 SX PERF. 3622'-25'

160 SX. SQUEEZE @ 1051-59' 1138'-70' ORDER 250 SX. 60/40 POZ. 8% GEL 3% CC

20 SX. GEL. 4 SX. HULLS HALLIBURTON CEMENT CO. KELLER WATER TRUCKS

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:30 PM Day: 25 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Pump Down BACK SIDE 2 SX. HULLS 100 SX. CMT. MIX.

MAX PSI 400\* CLOSE IN 150\* Pump Down 4 1/2" w/ 2 SX. HULLS 160 SX.

CMT. MIX. 5 SX. GEL. 25 SX. CMT. MIX. MAX. PSI. 1300\* CLOSE IN 1000\*

PLUG. COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

(observe this plugging.)

DATE \_\_\_\_\_

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 9403